

CONTENTS

Foreword.....	iii
---------------	-----

SECTIONS

1. Introduction.....	1
1.1 Background	1
1.2 Purpose	1
1.3 Scope	1
1.4 Sources	2
1.5 Use of Other PEI Recommended Practices	2
1.6 Regulations.....	2
2. Definitions	3
2.1 Aboveground Tank.....	3
2.2 Alarm Level.....	3
2.3 Alternative Fuel.....	3
2.4 API 12F Tank	3
2.5 API 650, Appendix J Tank	3
2.6 Atmospheric Tank	3
2.7 Attended Facility	3
2.8 Authority Having Jurisdiction (AHJ).....	3
2.9 Bonding	3
2.10 Bottom Loading.....	3
2.11 Class I Liquid	3
2.12 Direct Fill	3
2.13 Electrical Shutoff Switch	3
2.14 Flow Restriction Valve	3
2.15 Fuel.....	3
2.16 Generator Base Tank	4
2.17 Grounding.....	4
2.18 Listed	4
2.19 Loose Fill.....	4
2.20 Manifolderd Fill.....	4
2.21 Maximum Operating Level	4
2.22 Mechanical Shutoff Valve	4
2.23 Obround Tank.....	4
2.24 Operator(s).....	4
2.25 Overfill Alarm	4
2.26 Overfill Incident	4
2.27 Overfill Level	4
2.28 Overfill Prevention Device	4
2.29 Petroleum Product.....	4
2.30 Pumped Delivery.....	4
2.31 Qualified Personnel	4
2.32 Qualified Technician	4
2.33 Railcar Tanker	4
2.34 Remote Fill.....	4
2.35 Safety Data Sheet (SDS).....	4
2.36 Shutoff Level	5
2.37 Spill Kit	5
2.38 Stationary Tank.....	5
2.39 Storage Tank.....	5
2.40 Supply Tank.....	5
2.41 Tank Vehicle	5

2.42	Tank Vehicle Operator.....	5
2.43	Tight Fill.....	5
2.44	Top Loading	5
2.45	Unattended Facility	5
2.46	UL 80 Tank.....	5
2.47	UL 142 Tank.....	5
2.48	UL 2085 Tank.....	5
2.49	Ullage	5
2.50	Usable Ullage	5
2.51	Vent Whistle	5
3.	Safety	6
3.1	General	6
3.2	Responsibility.....	6
3.3	Chemical Hazards	6
3.4	Fire and Explosion Hazards	7
3.5	Electrical Hazards	7
3.6	Personnel Hazards.....	7
3.7	Fall Hazards.....	8
3.8	Personal Protective Equipment	8
3.9	Responding to Fuel Spills	8
3.10	Vehicle Hazards.....	8
4.	Elements of Effective Overfill Prevention	9
4.1	General	9
4.2	Qualified Personnel.....	9
4.2.1	Relevant Knowledge Areas.....	9
4.2.2	Attended Facilities	9
4.2.3	Unattended Facilities.....	10
4.3	Product Transfer and Emergency Response Procedures.....	10
4.3.1	Planning the Delivery	10
4.3.2	Arriving at the Site.....	10
4.3.3	Calculating Usable Ullage	11
4.3.4	Checking Equipment.....	11
4.3.5	Setting Up the Delivery	11
4.3.6	Initiating the Delivery	11
4.3.7	Monitoring the Delivery	11
4.3.8	Completing the Delivery.....	12
4.3.9	Emergency Planning and Response	12
4.4	Equipment Inspection, Maintenance and Testing	12
4.4.1	Inspection and Maintenance	12
4.4.2	Testing.....	13
4.4.3	Component Documentation	13
5.	Overfill Prevention Devices	14
5.1	General	14
5.2	Selecting Overfill Equipment.....	14
5.3	Testing Overfill Prevention Equipment	14
5.4	Types of Overfill Prevention	14
5.5	Mechanical Flow Shutoff and Flow Restriction Valves	15
5.5.1	Appropriate Uses.....	15
5.5.2	Limitations	15
5.5.3	Installation.....	15
5.5.4	Inspection and Maintenance	16
5.5.5	Testing.....	16
5.6	Electrical Shutoff Switches	16
5.6.1	Appropriate Uses.....	17
5.6.2	Limitations	17

5.6.3	Installation.....	17
5.6.4	Inspection and Maintenance	17
5.6.5	Testing.....	17
5.7	Electrically Operated and Mechanical Vent Alarms	17
5.7.1	Appropriate Uses.....	17
5.7.2	Limitations	18
5.7.3	Installation.....	18
5.7.4	Inspection and Maintenance	19
5.7.5	Testing.....	19
5.8	Mechanical Vent Whistles.....	19
6.	Special Situations.....	20
6.1	General	20
6.2	Manifolded Filling.....	20
6.2.1	Installation.....	20
6.2.2	Operation.....	20
6.3	Generator Base Tanks.....	21
6.3.1	Installation.....	21
6.3.2	Operation.....	21
6.4	UL 80 Tanks	21
6.4.1	Limitations	22
6.4.2	Installation.....	22
6.4.3	Inspection and Maintenance	22
6.4.4	Testing.....	22
6.4.5	Operation.....	22
6.5	Used Oil Tanks.....	22
6.5.1	Installation.....	23
6.5.2	Operation.....	23
6.6	Alternative Fuels	23
6.6.1	Operation.....	23
7.	Gauges.....	24
7.1	General	24
7.1.1	Appropriate Uses.....	24
7.1.2	Limitations	24
7.1.3	Installation.....	24
7.1.4	Inspection and Calibration	24
8.	Electrical Installation.....	25
8.1	General Requirements.....	25
8.2	Classifications	25
8.3	Electrical Equipment.....	25
8.4	Wiring.....	25
8.5	Intrinsically Safe	25
8.6	Cathodic Protection Systems.....	25
8.7	Grounding and Bonding.....	25
8.8	Provide Uninterrupted Power.....	26

APPENDICES

Appendix A:	Calculating the Installation Height of Overfill Prevention Devices	27
A.1	General	27
A.2	Vertical Cylindrical and Rectangular Tanks.....	27
A.3	Horizontal Cylindrical Tanks	28
A.4	Obround Tanks	29
Appendix B:	Publication Reference.....	31